| | Description of items | Per | Quantity |
|---|---|---|---|
| 19. | Channel iron sleepers (Departmental work) .. .. .. | Cwt. | .. |
| 20. | Steel rails 40 lbs. per yard (Departmental work) .. .. .. | ,, | .. |
| 21. | Teakwood doors 2" thick panelled with hinges, bolts, etc., complete .. | Sft. | 380 |
| 22. | Teakwood doors 1½" thick paneled do .. .. | ,, | 252 |
| 23. | Teakwood glazed windows, 1½" shutters with iron bars, etc. .. .. | ,, | 670 |
| 24. | Teakwood glazed semi-circular fan lights, 2" shutters .. .. | ,, | 104 |
| 25. | Do do 1½" shutters .. .. | ,, | 190 |
| 26. | Teakwood staircase with ornamental wooden railings on both sides with two coats of varnish, 157 sft. floor area .. .. .. | L. S. | .. |
| 27. | Teakwood ornamental railing with 2 coats of varnish .. .. | Rft. | 18 |
| 28. | Silver-grey silicate painting, 3 coats .. .. .. | Sqr. | 32·82 |
| 29. | Teakwood pipe duct corner, 1½" thick .. .. .. | Sft. | 268 |
| | FIRST FLOOR. | | |
| 1. | Coursed rubble stone masonry in surkhi mortar superstructure .. .. | Sft. | 17·231 |
| 2. | Stone slabs, 6" thick roughly dressed .. .. .. | ,, | 60 |
| 2a. | Do two line dressed .. .. .. | ,, | 60 |
| 2b. | Stone slabs 6" thick three line dressed .. .. .. | Sft. | 60 |
| 3. | Arch-work in cement concrete (specification same as given in ground floor item 6) | Cft. | 1624 |
| 4. | Stone quoins 1" chisel drafted .. .. .. .. | ,, | 87 |
| 5. | Stone cornice 9" deep nicely dressed .. .. .. | Rft. | 350 |
| 6. | Rolled steel I beams, hoisting and fixing only .. .. .. | Cwt. | 375 |
| 7. | Cement pointing (1, 2) .. .. .. .. | Sqr. | 154·40 |
| 8. | Cement concrete jack arch floor including 1st class Mangalore tile flooring on top cement pointed and cement plastering to jack arches with centrings (con. 1, 2, 4, and jelly not to exceed ¾" dia.) | ,, | 50·31 |
| 9. | Teak-wood glazed windows 1½" shutters with iron bars etc. .. .. | Sft. | 264 |
| 10. | Teak-wood glazed fan lights 1½" shutters .. .. | ,, | 69 |
| 11. | Teak-wood staircase with ornamental wooden railings on both sides, with 2 coats of varnish, floor area 152 sft. | L. S. | .... |
| 12. | Expanded metal grill work with painting etc., complete, (departmental work) .. | Sft. | .... |
| 13. | Silver gray silicate painting 3 coats .. .. | Swr. | 17·08 |
| | SECOND FLOOR. | | |
| 1. | Coursed rubble stone masonry in surkhi mortar .. .. .. | Cft. | 20,578 |
| 2. | Stone slabs 6" thick roughly dressed .. .. .. | Sft. | 274 |
| 2a. | Stone slabs 6" thick two line dressed .. .. .. | ,, | 274 |
| 2b. | Stone slabs 6" thick three line dressed .. .. .. | ,, | 274 |
| 3. | Archwork in cement concrete (specification same as item 6 of ground floor) .. | Cft. | 63 |
| 4. | Stone quoins 1" chisel drafted .. .. .. .. | ,, | 1·95 |
| 5. | Steel trusses 39' clear span ¼ rise, hoisting and fixing charges only .. | No. | 8 |
| 6. | Cement pointing (1, 2) .. .. .. .. | Sqr. | 208·83 |
| 7. | Corrugated Gal. iron roofing 22 B. W. G. sheets to overlap to corrugations at sides and 12" at ends with bolts screws and lead-washers etc. complete. | ,, | 62·40 |
| 8. | Gal. iron ridge sheeting 24" wide joints to lap 12" with bolts lead washers etc., complete. | Rft. | 130 |
| 9. | Bed-slab of trusses 3' x 2' x 6" with 4 bolt holes fixed complete .. .. | No. | 16 |
| 10. | Channel iron purlins, hoisting and fixing charges only .. .. | Cwt. | 161·6 |
| 11. | Teakwood work with wood oiling fixed complete .. .. | Cft. | 128·64 |
| 12. | Eave gutter built in brick in surki mortar and cement plastered with lead sheet living to bottom and sides. | Rft. | 264 |
| | NOTE.—The stone corbelling under the gutter will be measured under stone masonry lead sheeting to be not less than 1/16" thick. | | |
| 13. | Rain water down pipes 4" dia. 22 B. W. G. Gal. iron fixed with clamps, etc., complete. | Rft. | 1250 |
| 14. | Brick in mortar cornice, cement plastered 15" deep .. .. | Rft, | .... |
| | N.B.—The rate includes the brick work that goes into the wall | ,, | 94 |
| 15 | Binding wall 1½' x 1½' brick in mortar and cement plastered .. .. | ,, | 94 |
| 16. | Teakwood glazed windows 1½" shutter with iron bars .. .. | Sft. | 700 |
| 17. | Teakwood glazed circular ventilators 1½" shutter .. .. | ,, | 25 |
| 18. | Silvergray silicate painting, 3 coats .. .. .. | Sqr. | 16·25 |
| 19. | Expanded metal grill work with painting etc., complete) departmental work) .. | .... | .. |
| 20. | Fixing angle iron supports, foundation bolts etc., in the walls .. .. | No. | 200 |

*Dated 24th July* 1923.

Attention is invited to Notice No. S. 4337—C. P. S. of the 14th July 1923, calling for tenders for the supply of materials required for maintenance use in the Electrical Department for the half-year ending 31st December 1923. For full particulars, please see Part VI, pages 464 to 468 (both inclusive) of the *Mysore Gazette*, dated the 19th July 1923.

S. G. FORBES,
*Chief Electrical Engineer.*

## MYSORE STATE TROOPS.

*Abstract Notification.*

The attention of the public is invited to the detailed notification dated 10th July 1923, published on pages 606 and 607, Part IV of the *Myore Gazette*, dated 19th July 1923 regarding the amounts of field batta and gratuity due to members of the Mysore Lancers remaining undisbursed in this Department which may be claimed by the parties or their heirs before 1st September 1923.

B. CHAMARAJ URS, LT.-COL., S.B.,
*Chief Commandant.*